

KCCP LIMITED

(A Govt. of Kerala Undertaking)

"CLAY HOUSE", PAPPINISSERI PO. 670 561, KANNUR DT. KERALA

Telephone: 0497-2787671 & 2789633 Fax: 0497-2787281,

Website: Kccpl.in

E-mail: keralaclays@gmail.com

Ref: KCCP/TENDER/ 1540 /2026-27

Date: 03.09.2026

TENDER NOTICE

Sealed tenders are invited from interested parties for Supply, Installation, Testing, and Commissioning of CCTV Surveillance System at Kanjikode, Palakkad district - 678621.

Cost of tender form : Rs. 1,593/- (Including GST)
EMD : Rs. 3,500/-

Priced tender form may be obtained from our office up to 17.09.2026, 5.00 PM. Tender will be accepted up to 18.09.2026 at 2.00 PM and will be opened on 19.09.2026, 4.00 PM. Details if any can be obtained from our Administrative Office, Pappinisseri.

Sd/
MANAGING DIRECTOR

Specifications

Item No.	Parameter / Description	Minimum Technical Specifications Required	Unit	Qty
1	Network Video Recorder (NVR)	20-Channel IP NVR, supporting up to 8 MP resolution decoding, minimum incoming bandwidth 120/100 Mbps, min. 2 SATA interfaces supporting up to 10 TB capacity per SATA slot.	Nos	1
2	IP Outdoor Bullet Camera	2 MP IP Varifocal/Motorized Bullet Camera, Lens size 2.8 mm – 12 mm motorized zoom/focus, Minimum IR Distance 50 Meters, On-board Micro SD slot supporting up to 256 GB, Weatherproof IP67 rated metallic housing.	Nos	8
3	Smart PoE Switch	8 x Gigabit PoE Ports + 2 x Gigabit SFP Ports Smart Managed/Unmanaged Switch, Minimum total PoE Power Budget: 61 Watts.	Nos	2
4	Surveillance Hard Disk (HDD)	8 TB Enterprise/Surveillance-grade Hard Disk Drive suitable for continuous 24/7 high-definition recording.	Nos	1
5	Armoured Optical Fibre Cable (OFC)	Supply & Laying (S&L) of 2-Core Outdoor Single Mode Optical Fiber Cable.	Mtr	100
6	Category 6 UTP Cable	Supply & Laying (S&L) of 4-pair	Mtr	305

	with Conduit	Unshielded Twisted Pair (UTP) Cat-6 Cable laid through heavy-duty rigid PVC Conduit.		
7	Display Monitor	32-inch Full HD LED Monitor with HDMI/VGA input compatibility for 24/7 operation display.	Nos	1
8	Outdoor Enclosure Rack	6U Weatherproof Outdoor Wall/Pole-Mount Equipment Enclosure/Rack with lockable front door and IP rating suitable for outdoor deployment.	Nos	1
9	Indoor Rack	9U Wall-Mount/Floor-Mount Indoor Rack for housing NVR, network switches, power supplies, and accessories.	Nos	1
10	Media Converter	1 Single-Mode Optical-to-Ethernet Gigabit Media Converter Set/Pair.	Pair	1
11	HDPE Piping	Supply & Laying (S&L) of High-Density Polyethylene (HDPE) Protection Pipe for outdoor underground/surface cable routing.	Mtr	160
12	HDMI Connectivity	High-speed HDMI Cable (suitable length, minimum 4K supported standard).	Nos	1
13	Installation & Commissioning Services	Labour charges including complete fixing, termination, routing, testing, integration, and commissioning of the entire CCTV surveillance system.	Job / Lot	1

